



Summary of test results:

Maximum power degradation: allowed max. 5 %
measured max. 0.73 %

The measured degradation is below the allowed degradation.

Dry insulation resistance: required min. 15.5 M Ω
measured >500 M Ω

The measured dry insulation resistance is above the limit.

Wet insulation resistance: required min. 15.5 M Ω
measured >500 M Ω

The measured wet insulation resistance is above the limit.

Visual inspection: No findings

Ground continuity test: allowed max. 0.1 Ω
measured max. 0.0174 Ω

Bypass diode functionality test: Still functional after test

The complete test results and the relevant bill of materials are given in Test Report No.: TRPVM- ET-20221016-187-14

VDE Renewables GmbH

Zhiyao Wang

Dean Wen

Shanghai, 2023-02-12

