





### Summary of test results:

**Maximum power degradation:** allowed max. 5 %  
measured max. 0.75 %

The measured degradation is below the allowed degradation.

**Dry insulation resistance:** required min. 15.5 MΩ  
measured >500 MΩ

The measured dry insulation resistance is above the limit.

**Wet insulation resistance:** required min. 15.5 MΩ  
measured >500 MΩ

The measured wet insulation resistance is above the limit.

**Ground continuity test:** required max. 0.1Ω  
measured max. 0.0112Ω

The measured ground continuity test is below the limit.

**Visual inspection:** No findings

**Bypass diode functionality test:** Still functional after test

The complete test results and the relevant bill of materials are given in Test Report No.: TRPVM- ET-20221016-187-6.

### VDE Renewables GmbH

**Zhiyao Wang**

Shanghai, 2023-02-02

**Dean Wen**

